MARYLAND HISTORICAL TRUST NR-ELIGIBILITY REVIEW FORM

NR	Eligible:	yes	
		no	

Property Name: Rawhouser House Inventory Number: BA-2026
Address: 17004 York Road City: Parkton Zip Code: 21120
County: Baltimore USGS Topographic Map: Hereford, MD
Owner: Stanley A. Cohn and Karen P. Cohn
Tax Parcel Number: 246 Tax Map Number: 22 Tax Account ID Number:
Project: Hereford Tower Project Agency: FCC
Site visit by MHT Staff: X no yes Name: Date:
Eligibility recommended Eligibility not recommended X
Criteria: ABCDC Considerations: ABCDEFG None
Is the property located within a historic district? X noyes Name of district:
Is district listed? X noyes Determined eligible? X noyes District Inventory Number:
Documentation on the property/district is presented in: MIHP form; Rotenstein 2000
The Rawhouser House is a 2½ -story log building constructed on a masonry wall foundation. The side-gabled building measures five bays by four bays and has two internal brick chimneys. The oldest block of the building is rectangular and the plan has been modified through several additions. There are wood double-hung sash windows (6/6 lights) and an enclosed shed roof front entry porch. There also is a shed roof side porch in a rear ell addition. The building is clad by metal siding and the original block's roof is clad by metal shingles and has cornice returns. Standing seam metal and gable dormers may be found on the roof of the rear ell addition. Additions and alterations include several fenced kennel buildings in the rear and a surfaced parking area in former side and rear yards. The building was constructed between ca. 1834 and 1839, probably by Joshua Rawhouser. In 1981, the building was converted into a veterinary hospital (Mount Carmel Animal Hospital). Although one of the older surviving buildings in Hereford, the Rawhouser House and its grounds have undergone extensive modifications in its transition from a residence into an animal hospital. The property retains little integrity and is not eligible for listing in the National Register of Historic Places.
Prepared by: David S. Rotenstein Date Prepared: 9/07/2000
MARYLAND HISTORICAL TRUST REVIEW Eligibility recommended Eligibility not recommended
Criteria: A P C D Caribbath
Criteria:ABCD Considerations:ABCD_EF_GNone Comments:ABCD
(Marile 11/16/10)
Reviewer, Office of Preservation Services
Reviewer, Ne program 6 2 0 Date

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No.

BA-2026

4 Name 65	·			
1. Name of P		(indicate preferr	ed name)	
historic		ser House		
other	Naylor	House		
2. Location				
street and number	17004	ork Road		not for publication
city, town	Parktor	1		vicinity
county	Baltimo	ore		
3. Owner of F	Property	(give names and mai	ling addresses of all ow	vners)
name	Stanley	A. Cohn and Karer	n P. Cohn	
street and number	17004 Y	ork Road		telephone
city, town	Parkton		state MD	zip code 21120
Contributing Rescontributing Rescontributing Rescontributing Rescontributing Rescontributions	ource in Nation ource in Local ole for the Nation gible for the Na SS/HAER	onal Register/Maryland Reg tional Register/Maryland R	gister	
6. Classificati	ion		· · · · · · · · · · · · · · · · · · ·	
district	wnership public X private both	Current Function agricultureX commerce/tradedefensedomesticeducationfunerarygovernmenthealth careindustry	landscape recreation/culture religion social transportation work in progress unknown vacant/not in use other:	Resource Count Contributing Noncontributing

7. Description		Inventory No.	BA-2026
Condition			
excellent good _X fair	deteriorated ruins X altered		

Prepare both a one paragraph summary and a comprehensive description of the resource and its various elements as it exists today.

The Rawhouser House is a 2½ -story log building constructed on a masonry wall foundation. The side-gabled building measures five bays by four bays and has two internal brick chimneys. The oldest block of the building is rectangular and the plan has been modified through several additions. There are wood double-hung sash windows (6/6 lights) and an enclosed shed roof front entry porch. There also is a shed roof side porch in a rear ell addition. The building is clad by metal siding and the original block's roof is clad by metal shingles and has cornice returns. Standing seam metal and gable dormers may be found on the roof of the rear ell addition. Additions and alterations include several fenced kennel buildings in the rear and a surfaced parking area in former side and rear yards.

8. Signifi	cance	Ir	nventory No. BA-202	6
Period 1600-1699 1700-1799 1800-1899 1900-1999 2000-	Areas of Significance agriculture archeology X architecture art commerce communications community planning conservation	Check and justify below economics education engineering entertainment/ recreation ethnic heritage exploration/ settlement	health/medicine industry invention landscape architecture law literature maritime history military	performing arts philosophy politics/governmen religion science social history transportation other:
Specific date:	s ca. 1834-1950	Architect		
Construction	dates 1834-1839	Builder		
Evaluation fo	r:			
X_ Natio	onal Register	Maryland Register	not	t evaluated

Prepare a one-paragraph summary statement of significance addressing applicable criteria, followed by a narrative discussion of the history of the resource and its context. (For compliance reports, complete evaluation on a DOE Form - see manual.)

The building was constructed between ca. 1834 and 1839, probably by Joshua Rawhouser. In 1981, the building was converted into a veterinary hospital (Mount Carmel Animal Hospital). Although one of the older surviving buildings in Hereford, the Rawhouser House and its grounds have undergone extensive modifications in its transition from a residence into an animal hospital. The property retains little integrity and is not eligible for listing in the National Register of Historic Places.

Maryland Historical Trust Maryland Inventory of Historic Properties Form

Inventory No. BA-2026

Name	Rawhouser House
Continu	uation Sheet
Number	8 Page1

HISTORIC CONTEXT

MARYLAND COMPREHENSIVE PRESERVATION PLAN DATA

Geograpi	Geographic Organization:				
Chronolo	Chronological/Developmental Period(s):				
Historic P	Period Theme(s):				
Resource	Туре:				
	Category:				
	Historic Environment				
	Historic Function(s) and Use(s):				
	Known Design Source:				

9. Major Bibliographical References

Inventory No. BA-2026

Baltimore County Council (1991); Brooks, N. A., and E. G. Rockel (1979); Clemens and Clemens (1983); McGrain (1980)

10. Geographical Data

Acreage of surveyed property

20,301 sq. ft.

Acreage of historical setting

20,301 sq. ft.

Quadrangle name

Hereford, MD

Quadrangle scale

1:24,000

Verbal boundary description and justification

The boundaries for this property conform to the tax parcel boundary: Map 22, Parcel 246.

11. Form Prepared By

name/title	David S. Rotenstein, Ph.D./Historian		
organization	URS/Dames & Moore	date	9/07/2000
street and number	7101 Wisconsin Avenue, Suite 700	telephone	301-652-221
city or town	Bethesda	state MD	zipcode 20814-4870

The Maryland Inventory of Historic Properties was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.


return to:

Maryland Historical Trust

DHCD/DHCP

100 Community Place Crownsville MD 21032

410-514-7600





BA-2026 1/3 Rawhouser House Naylor House 17004 York 2009 Baltimore County, Mary land David S. Rote stein 8/22/00 MD SHPO View of Fawhouser House, to the west from across Yor & Road.



BA-2026 2/2 Bankouse House Naylor House 17004 York Road Boltimore County, Mary and David S. Roten Stein 8/22/2000 View of the hawhouser House, to the hortheast, showing side elevation and



BA-2026 Rawhouser House Waylor House 17004 York Road Baltimore Courty, Mary land David S. Roterstein 8/22/2000 MD SHPO View of the Rawhouser House, to the northeast, in vear of building showing kennels and additions.

BA 2026

RAWHOUSER HOUSE/ NAYLOR HOUSE

1834-1839

HEREFORD

PRIVATE

This house is log beneath its white aluminum siding and is one of the earlier structures in the village, probably built by Joshua Rawhouser on the first village lots. The 1841 tax ledger showed \$500 worth of improvements on the lot. Charles C. Wittig who purchased the house in 1864 appeared in directories as a tailor. It was in the Diven family from 1897 to 1950. This is a duplex in vernacular style, close to the road; fenestration and porch layout is asymetrical. The rear wing produces an L-shaped plan and the rear wing is 1-½ stories high; that wing ends with a shed-roofed segment with a single dormer that faces the side yard.

MAGI 0320265404

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME						
HISTORIC	RAWH	OUSER HOUSE				•
AND/OR COM	IMON					
	Naylo	or House				
2 LOCAT	TON					
STREET & NUI	MBER					
17,00	4 York	Road				
CITY, TOWN				CONGRESS	IONAL DIST	RICT
	Hereford vicinity of		VICINITY OF	2nd		
state Maryl	and			COUNTY Balti	more C	ounts
3 CLASS	IFICA	TION		20202	MOTO C	Ourcy
CATEG	ORY	OWNERSHIP	STATUS		Doro	1 PF 5 1 PW 4 4 4 4 4
DISTRICT		PUBLIC	X OCCUPIED	ACRI	CULTURE	ENT USE
X_BUILDING	(s) X	PRIVATE	UNOCCUPIED		MERCIAL	MUSEUM PARK
STRUCTUE	RE _	ВОТН	WORK IN PROGRESS		ATIONAL	X PRIVATE RESIDENCE
SITE		PUBLIC ACQUISITION	ACCESSIBLE		RTAINMENT	
OBJECT	_	_IN PROCESS	X YES: RESTRICTED		RNMENT	SCIENTIFIC
jan ene.	-	_BEING CONSIDERED	YES: UNRESTRICTED	INDU:		TRANSPORTATION
			NO	MILIT	ARY	OTHER:
4 OWNE	ROFF	ROPERTY				
NAME						
Josiah	ı L. N	aylor		Telephone	# - 320	9-6577
STREET & NUM					11 . 32.	0377
17,004	York	Road				
CITY, TOWN				5	TATE , Z	ip code
Parkto			VICINITY OF			and 21120
5 LOCAT	ION C	F LEGAL DESCR	IPTION			
COURTHOUSE.				Liber #:	TBS]	1907
REGISTRY OF E	DEEDS, ETC.	County Courts B	uilding	Folio #:	1	.83
STREET & NUM	IBER					
^(TV T) 1 () 1		401 Bosley Avent	ie			
CITY, TOWN		Towson			TATE	orbitales causas en la libra de Planacia en reproduction menoració capado, masse por el riches (a
D Dran - /	7 0 7 % T PS				Maryla	nd 21204
C KEPKE	SENT/	ATION IN EXISTI	NG SURVEYS			
TITLE						
NO	NE					
DATE					<u> </u>	A Committee of the Comm
			FEDERAL _	_STATECOUNTY	LOCAL	
DEPOSITORY FO						The second secon
CITY, TOWN						
				ST	ATE	
						

7 DESCRIPTION

CONDITION

CHECK ONE

CHECK ONE

 $\begin{array}{c} _\texttt{EXCELLENT} \\ \underline{X}_{\texttt{GOOD}} \\ _\texttt{FAIR} \end{array}$

__DETERIORATED
__RUINS
__UNEXPOSED

_unaltered
Xaltered

X_ORIGINAL SITE
__MOVED DATE_____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

The Rawhouser or Naylor House is one of the earlier town houses of Hereford, set close to the road and very close and aligned with the large brick house to the north (BA 2025). It is a duplex log house of two stories now totally disguised by white aluminum siding. The bays are laid out irregularly, as are the entrances; the main porch is asymetrical. Style is vernacular.

The main (or east) facade is six bays and there is a three-bay, shed-roofed entrance porch that embraces the third, fourth, and fifth bays, counting from the south. These bays contain two doors which flank a window in the fourth bay. The doors are paneled and contain six lights each. A narrow rectangular transom tops each of the door frames. The porch deck is of wood, four steps above grade. Roof supports are contemporary wrought iron and there are porch railings and a stair railing of similar wrought iron. The space under the porch is filled in by concrete block.

The four windows at first-story level are 6-over-6 double-hung sash windows, fitted with decorative shutters. At second-story, there are four similar windows, used in the bays directly over bays Number one, three, four, and six of the story below. There is a box cornice, a result of re-covering with aluminum. The main block roof is gabled, and there is an inside end-chimney at the north end of the house; this chimney is a rectangular cross-section and its flue covered with a protective slab. The south end of the house has a plain inside end-chimney.

The south end walls of the main block are blank except for two square gable-end windows of four lights each; the gable pediment is filled in with ribbed sheet metal, painted red. The north end wall of the main block is three bays deep, punctuated with one bay of typical windows, also with shutters in the main block. These windows open into a very narrow yard between this house and the blank brick end-wall of the structure to the north.

The house is L-shaped in overall plan, and its rear wing is 1½ to two stories high, flush on its north wall with the north end of the main block. The southside of this wing opens on the garden. The westernmost extension of the rear wing is a 1½-story "half flounder" design—a shed-roofed segment with a single dormer. Four bays are found in the southside of the south wall, facing the garden and providing two doors and two windows at the first-story level. The west end of this wing is blank, unfenestrated.

CONTINUE ON SEPARATE SHEET IF NECESSARY

PERIOD	AF	REAS OF SIGNIFICANCE CH	IECK AND JUSTIFY BELOW	
KEHISTORIC	ARCHEOLOGY-PREHISTORIC	COMMUNITY PLANNING	LANDSCAPE ARCHITECTURE	RELIGION
1400-1499	ARCHEOLOGY-HISTORIC	CONSERVATION	_LAW	SCIENCE
1500-1599	AGRICULTURE	ECONOMICS	LITERATURE	SCULPTURE
1600-1699	XARCHITECTURE	EDUCATION	MILITARY	_SOCIAL/HUMANITARIAN
1700-1799	ART	ENGINEERING	MUSIC	THEATER
X.1800-1899	X COMMERCE	EXPLORATION/SETTLEMENT	PHILOSOPHY	TRANSPORTATION
1900-	COMMUNICATIONS	INDUSTRYINVENTION	POLITICS/GOVERNMENT	OTHER (SPECIFY)
SPECIFIC DAT	ES 1834-1839	BUILDER/ARCI	HITECT	

STATEMENT OF SIGNIFICANCE

This house, which is log beneath its contemporary outer covering, was one of the earlier structures in the village laid out on the former Merryman tracts called "Hereford Resurveyed." It was probably built by Joshua Rawhouser, who acquired the lot for \$30 from Ashton Alexander in April of 1834. (1) Alexander had married into the Merryman family.

Rawhouser took out a mortgage for \$103 in 1839 and the 1841 Assessor's Field Book shows him with \$500 worth of improvements on his lot in Hereford, also two cows and six hogs. (2) Many of the residents of Hereford used the deep and spacious lots to raise livestock, judging from the tax records. On the 1852 Assessment, Rawhousel (sic) had \$650 worth of improvements and a slave named Maria. (3) His name also appeared on the 1850 county map by J. C. Sidney.

In 1854, Rawhouser and wife, Elizabeth A., sold to Edward C. Royston for \$650. Royston held it until 1864, selling to Charles C. Wittig. (4) The 1877 atlas shows the house, but there is no room for the owner's name. Wittig was listed as a tailor at Hereford in the 1878 business directory. (5) The 1876 tax ledger charged Wittig with \$450 worth of "Stock in Trade--Tailoring." He also had one heifer, four shoats, and "farming implements with harness." The Wittig house contained \$250 worth of furniture, suggesting that the little town was a comfortable and prosperous place. The 1896 Tax Ledger charged him with but \$100 in furniture and \$20 for "average amount of stock on hand." (7)

In 1897, Wittig's son and his widow sold the place to George E. Diven for \$650. (8) The house remained in the Diven family until 1950. By the 1911 tax ledger, George Diven's dwelling had reached the value of \$900; there was an outbuilding worth \$75. In 1915, a garage worth \$50 was added to the list, plus an auto, an R.C.H. model, worth \$300. (9)

The Diven house was listed as two stories; 16 by 14 feet in one segment and 18 by 38 in another, total value \$1126. After 53 years in the same family, William T. Diven, executor of George T. Diven, conveyed the place to the pres-CONTINUE ON SEPARATE SHEET IF NECESSARY ent owners in 1950. (11)

(continued)

CONTINUATION SHEET NO. 1, ITEM 8, PAGE 2

RAWHOUSER HOUSE

NOTES:

- 1. Baltimore City Deeds, AI 236:344.
- 2. Baltimore City Deeds, TK 297:330. Also, Seventh District Assessor's Field Book, 1841, n.p.
- 3. 1852 Assessment, District 7 (Hall of Records #8256).
- 4. Baltimore County Deeds, GHC 29:380; JHL 45:468.
- 5. J. Frank Lewis & Co., Maryland Directory (Baltimore, 1878), p. 530.
- 6. B.C. Assessor's Field Book, 1876, District 7, n.p.
- 7. Tax Ledger, 1896, District 7, Entry #639-148.
- 8. B.C. Deeds, LMB 223:21.
- 9. Tax Ledger, 1911, District 7, f. 483.
- 10. Tax Ledger, 1918, District 7, f. 483.
- 11. B.C. Deeds, TBS 1907:183.

BA-2026

9 MAJOR BIBLIOGRAPHICAL REFERENCES

RAWHOUSER HOUSE

Baltimore County Tax Ledgers and Deed Books.

CONTINUE	ON	SEPARATE	SHEET	IF	NECESSARY
----------	----	----------	-------	----	-----------

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY 0.47

VERBAL BOUNDARY DESCRIPTION

Beginning on westside of York Road:

N86° 15'W 12 perches to Green Alley

N1° 15'W 6 perches along Green Alley

S86° 15'E 14 perches center of York Road

S1° 15'E 6 perches along center of York Road

Thence with a straight line to BEGINNING.

(Map 22, P246)

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE NONE

COUNTY

NONE

STATE

NONE

COUNTY

NONE

III FORM PREPARED BY

NAME / TITLE

John W. McGrain, Sites Surveyor

ORGANIZATION	DATE
Baltimore County Office of Planning and	Zoning March 13, 1980
STREET & NUMBER	TELEPHONE
401 Bosley Avenue	494-3495
CITY OR TOWN	STATE
Towson	Maryland 21204

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.


The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust

The Shaw House, 21 State Circle

Annapolis, Maryland 21401

(301) 267-1438





RAWHOUSER HOUSE BA 2026
Baltimore County, Maryland
J. McGrain, OCT 1979
Neg. located at MHT
Main (east) facade